



2x6 TOP PLATE

REMOVABLE BREAKAWAY CHANNELS
(VERTICAL) 2" ON BOTH SIDES OF EACH
STUD x 1 1/2" DEEP (2 1/2" BEHIND DRYWALL FACE).

TYPICAL EXT.
BRICK WALL CONSTRUCTION
4" BRICK VENEER TIED TO WALL
W/METAL VENEER TIES
@ 24" O.C. HORIZONTALLY &
16" O.C. VERTICALLY
1" AIRSPACE
HOUSEWRAP AIR BARRIER
7/16" OSB PANEL SHEATHING
TYPE 1 EXPANDED POLY-STYRENE
(1 LB DENSITY) INSULATION PANEL
2x6 STUD WALL @ 16" O.C.
1/2" AIR SPACE
6mil POLY AIR VAPOUR BARRIER
1/2" GYPSUM BOARD

2 REMOVABLE BREAKAWAY CHANNELS
(HORIZONTAL) 3" HIGH x FULL WIDTH x 1 1/2" DEEP
48" & 51" OFF FLOOR FOR SWITCHES

13" TOTAL ASSEMBLED
WALL THICKNESS

2 REMOVABLE BREAKAWAY CHANNELS
(HORIZONTAL) 3" HIGH x FULL WIDTH x 1 1/2" DEEP
14" & 17" OFF FLOOR FOR RECEPTACLES

2x6 BOTTOM PLATE

1 3/4" EZ SHEET

POURED/BLOCK FOUNDATION WALL
(10" THICK SHOWN)



TYPICAL BRICK VENEER WALL SECTION
WITH INSULATED RIM JOIST
(POURED/BLOCK FOUNDATION)

EZ SIPS

DATE: FEB-02-14 DRAWN: OC

SCALE: 3/4"=1'-0" APPROVED:

DWG NO: EZ SIPS-2X6 / 4B